BILL OF QUANTITIES

BOQ-0002

QA Civil A 01721613

10 Nov 2026

+919801721611 | qa.civil.a.01721613@example.com

Work G+1 residence – civil works, Mysuru

Client QA Client **Phone** 9000000011

Project QA Site Two **Site** Mysuru

No.	Description of work	Unit	Qty	Rate (Rs.)	Amount (Rs.)
Earthwork					
1	Excavation for foundation in ordinary soil up to 1.5 m depth	cum	85	320.00	27,200.00
2	Back filling with excavated earth in layers, watered and rammed	cum	40	180.00	7,200.00
Concrete					
3	PCC 1:4:8 bed under footings, 100 mm thick	cum	12	5,500.00	66,000.00
4	RCC M20 for footings, columns, beams and slab incl. shuttering	cum	48.5	8,900.00	4,31,650.00
Masonry					
5	230 mm brick masonry in CM 1:6	sqm	310	1,150.00	3,56,500.00

Sub total	Rs. 8,88,550.00
GST @ 18%	Rs. 1,59,939.00
Grand total	**Rs. 10,48,489.00**

Notes & terms

Rates valid for 30 days. Payment: 20% advance, balance on stage completion.

Quantities are estimates; final billing is on measured work.

For QA Civil A 01721613

Authorised signature: _____